



**WORK INSTRUCTIONS FOR ENGINEERS**

Compiled by : \_\_\_\_\_ CCM

Checked by : \_\_\_\_\_ TYC

Approved by : \_\_\_\_\_ GSS

**OP-3-32. CHECKLIST FOR SUPERVISION OF  
SHEET PILE INSTALLATION (EXCAVATION  
WORK)**



**CHECKLIST FOR SUPERVISION OF SHEET PILE INSTALLATION (EXCAVATION WORK)**

**32. CHECKLIST FOR SUPERVISION OF SHEET PILE INSTALLATION (EXCAVATION WORK)**

<b>1.0</b>	<b>PRELIMINARIES</b>		
1.1	<p><b>GEOTECHNICAL DESK STUDY</b> – Review of available documents and data of the site and adjacent areas including SI reports, geological maps, topography plan and etc.</p> <ul style="list-style-type: none"> <li><input type="checkbox"/> Drawings showing the layout of the sheet piles and details of the bracing.</li> <li><input type="checkbox"/> Proposed method statement.</li> <li><input type="checkbox"/> A copy of SI report or selected representative boreholes.</li> <li><input type="checkbox"/> Location of site with respect to geological conditions.</li> </ul>		
<b>2.0</b>	<b>ITEMS TO PREPARE FOR SITE SUPERVISION</b>		
2.1	<ul style="list-style-type: none"> <li><input type="checkbox"/> Site and Location Plan.</li> <li><input type="checkbox"/> Construction drawings.</li> <li><input type="checkbox"/> Scale, ruler and pull tape.</li> <li><input type="checkbox"/> Compass &amp; Slope Meter (if required).</li> <li><input type="checkbox"/> Photography Equipment (eg. Digital Camera, films, batteries).</li> <li><input type="checkbox"/> Writing Pad and Notes.</li> <li><input type="checkbox"/> Pen, Markers &amp; Spray Paint (if necessary).</li> <li><input type="checkbox"/> Safety equipments (Safety helmets, boots, etc).</li> </ul>		
<b>3.0</b>	<b>SUPERVISION PROCEDURES</b>		
3.1	Confirm the exact location at site where works are to be carried out.		
3.2	Confirm the Reference Direction of site using <u>Compass</u> with the references on <u>Site Plan / Map</u> .		
3.3	<p>Check/ consult the client / engineer (person in-charge) to understand the works to be carried out.</p> <p>Obtain a verbal briefing on the background of the site, noting down important events and dates.</p>		
3.4	<p>Confirm the sequence of works to ensure:</p> <ul style="list-style-type: none"> <li><input type="checkbox"/> Proper installation of sheet piles using recommended driving methods (e.g. closure of cofferdam and driving guide).</li> <li><input type="checkbox"/> Completion of works on time – see schedule, check and extrapolate.</li> </ul>		
3.5	<p>Confirm the following items are available / in working condition at site:</p> <ul style="list-style-type: none"> <li><input type="checkbox"/> Sheet piles, struts, king piles, bracing beams &amp; walers                             <ul style="list-style-type: none"> <li>o Correct size and length as specified in Drawings.</li> <li>o No defects spotted (e.g. damaged toe sides, head, twisted, etc).</li> <li>o Sufficient numbers for the completion of the works.</li> <li>o Proper storage of piles.</li> </ul> </li> <li><input type="checkbox"/> Driving guide of adequate length, fit and robust to ensure minimal movement.</li> <li><input type="checkbox"/> Spacer blocks for leading pile to prevent deviations from line.</li> <li><input type="checkbox"/> Vibro-hammer in working condition.</li> <li><input type="checkbox"/> Boring machine in working condition if preboring is required.</li> <li><input type="checkbox"/> Lifting crane of sufficient capacity and boom length – Bearing capacity check to ensure safety.</li> <li><input type="checkbox"/> Means of transport for excavated materials (No excavated materials are to be placed near to the pit) as surcharge to the sheet pile wall.</li> <li><input type="checkbox"/> Pumps                             <ul style="list-style-type: none"> <li>o In good working condition and of adequate capacity.</li> <li>o Provision of spare units to replace any malfunctioned unit immediately.</li> </ul> </li> <li><input type="checkbox"/> Welding unit (if necessary).</li> </ul>		



**CHECKLIST FOR SUPERVISION OF SHEET PILE INSTALLATION  
 (EXCAVATION WORK)**

<p><b>3.6</b></p>	<p>During the progress of the works, ensure that the following are practised at all times:</p> <ul style="list-style-type: none"> <li>❑ Proper handling of sheet piles.</li> <li>❑ No surcharge (excavated materials, excessive loads from machineries, etc) is allowed around the perimeter of the pit.</li> <li>❑ No water ponding / flooding around the perimeter of the pit for a sustained period of time.</li> <li>❑ Adequate depth of pre-boring (if specified).</li> <li>❑ No unsuitable materials are to be used as backfill for the pre-bored holes.</li> <li>❑ Adequate depth for interlock of sheet piles.</li> <li>❑ Sheet piles are driven to the correct penetration depth.</li> <li>❑ Deviations and leaning (transverse or longitudinal) of sheet piles is within tolerance limit.</li> <li>❑ Construction of struts, waler and bracing beam to Specifications and Drawings in particular the connection with proper contact / seating.</li> <li>❑ Construction of king pile to Specifications and Drawings and adequate penetration depth is achieved.</li> </ul>		
	<p><b>Signature by Engineer</b></p>		

